



19<sup>th</sup> January 2018

## **Notice invitation for tender /quotation**

Appropriate quotation/tender is invited in sealed cover from eligible bidder/supplier vendor for making and supply of the following items to be used in the Play Ground, 27 Canal East Road, Kolkata -54 of Scottish Church College.

### **Items**

Installation of flood light pole

### **Quantity**

Details given below

This quotation is to be addressed to the Teacher-In-Charge, Scottish Church College and has to be submitted to the Teacher-In-Charge's office in Scottish Church College, at 1 & 3 Urquhart Square, Kolkata - 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from 20-1-2018 which will close on 29-1-2018. The Selection /opening will be made in the College office at 3:00 P.M. on 30-1-2018.

The Authorities of the College reserve the right / discretion for selection based on experience, amount, quality of the bid & bidder.

**Dr. Arpita Mukerji**  
**Teacher - In - Charge**

Teacher-in-Charge  
Scottish Church College  
Kolkata-700 006

BoQ

To

Scottish Church College

3 ,Urquhart Square.Kolkata - 6

Sub :- INSTALLATION OF FLOOD LIGHT POLE AT BAG MARI PLAY GROUND

SL No	Description of work	Qty
1	Fixing of flood light pole and 1" dia hole on the lower portion of the pole for entry of the wire Base pole painting of red oxide and two coats of silver white aluminium paint. The poles shall have extra provided and fixed by laying 5'x2'x2' (length, breadth and width) cement concrete block in the ratio 1:3:6 and block be continued up to 1 feet above the ground level including surface plastering the job including excavation of pole with 4 feet deep and refilling the same after installation of the pole and with holes at top of the pole for fixing ring type GI bracket as required	4Nos.
2	Fixing of flood light pole and 1" dia hole on the lower portion of the pole for entry of the wire Base pole painting of red oxide and two coats of silver white aluminium paint. The poles shall have extra provided and including surface plastering the job including excavation of pole with 4 feet deep and refilling the same after installation of the pole and with holes at top of the pole for fixing ring type GI bracket as required	4Nos.
3	Supply and fixing of dust and weather proof gasket 250mm x 200mm x 150mm deep box nominal size of 16 SWG thick MS sheet cable looping box with the existing pole with MS clamp made out of 25mmx3mm thick flat iron with suitable nuts and bolts complete with hinged cover and locking screws earth studs neoprene gasket suitable for Nos 8 pole mounted including supply and fixing one no 10 Amp MCB carrier with base and 4 way 63 Amp terminal block suitable to receive PVC armoured cable fixed on suitable size Bakelite sheet base complete with connection painting as required .	8Nos.

SL No	Description of worke	Qty
4	<p><b>Earthing</b>  60 mm GI galvanized pipe ith Tin plated outside  40 mm GI heavy galvanized pipe inside with CCM Gel chemical filled around 40 mm pipe .  1+ Bag of Marbengy -50 Backfill compound for 2 meters type</p>	4 set
5	<p>Erection ,testing and commissioing of 1 x HPI-T 400 Watt Integral flood lights with all the accessories including assembling and making accessories including assembling and making connections and fixing of all the accessories as require.</p>	64Nos.
6	<p>Supply and drawing of 2x2.5 Sqmm PVC insulated copper flexible cable in tubular pole for providing supply to the flood lights pole as required (Havells/polycab)</p>	1200 Mtr.
7	<p>Shifting of the existing pole from its existing location and light</p>	l/s