

Scottish Church College

1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /06/2024-25 Dated 21-06-2024

Contact: Mr. Shibnath Bhattacharyya (M-98362-72199)
Mr. Monojit Mondal (M- 9123086001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for refurbishment to the rooms on first floor of north /west corner of Scottish Church College with water tightening the parapet and extension of toilet on roof.

Sl. No.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
A					
1	Preparing temporary scaffolding work with bamboo and rope with necessary platform for and dismantling after work .	Sq.mt.	169.75		
2	Carefully dismantling of all types of masonry i.e. brick work etc. as per requirement with cleaning debris etc.	One item	L.S.	Whole job	
3	Carefully deplastering /removal of damaged and effected plaster with cleaning Brick Joints from old mortar with brush and chisel rods including cleaning debris	Sq.mtrs	48.50		
4	Replastering with lime mortar (1:3) in 20mm to 25 mm thick mixing with water prospering compound with curing complete.	Sq.mtr	48.50		
5	Provision for shifting of different materials from the room (zonal centre)to attend following work to prevent any damage (almirah, chair, table etc)	One item	Whole job	L.S.	
6	Two coats lime wash with best quality lime mixing with ddl /glue with smoothing surface after preparing base including etc.	Sq. mtrs	238.67		
7	Repairing the doors and windows of both room with covering the bottom portion of windows with teak wood ply (04 nos) to prevent further openings (Proposed Chemical Research Lab)	One item	Whole job	L.S.	
8	Synthetic enamel paint to the doors and windows in double coats after preparing base including all.	Sq. mtr	90		



9	Flooring work to Zonal Centre with non skid / mat finish vitrified tiles (24" x 24") in proper level on ready made packeted mortar with pointing to the tile joints including finishing after preparing base of existing A.S. Flooring .	Sq. mtrs	51.17		
10	Provision for continuous of continuous ones table with "KOTA STONE" top to Proposed "Chemical Research Lab" through the "west" long wall and "north south" short wall in 0.60 mt width with necessary brick work	Mt.	10.70		
11	Provision for fixing "Aluminium "doors in "AL" frame work with frostrated glass at top and laminated ply at bottom with locking arrangement including all.	Sq. mtr	4.50		
12	Revival of electric line to the rooms with other facilities i.e. A.C. point , fan and other requirement (as suggested by the Authority)	One item	L.S.	Whole job	
13	Stretching of water connection to the proposed "Chemical Research Lab" as per requirement (as per suggested by the Authority)	One item	L.S.	Whole job	
B	Roof water tightening of related Rooms				
1	Raking out to loosened and damaged tar felt from the parapet with raking the perforated plaster including cornice as detected	Sqmt	25.00		
2	Replastering with lime mortar (1:3) in 20mm to 25 mm thick mixing with water proofing compound with curing complete	Sq.mtr	18.75		
3	Water proofing work on parapet and cornice by applying two coats Asian Paints Smart Care damp proof liquid after preparing base from dust, algae, and other materials	Sq.mtr	30.00		
4	Raking out the deep seated root of the trees from the Roof and Parapet joint with great care with due proper water tightening to prevent in grass of water to the structure	One item	Whole job	3 nos	
C	Extension of toilet non roof				
1	Preparing temporary scaffolding work with bamboo and rope with necessary platform and dismantling after work.	Sq.mtr	20.00		
2	Carefully dismantling of all types of brick masonry, damaged floor and also damaged corrugated tin Shade of existing toilet with its door .	Whole job	L.S.	One item	



3	1 st class brick work with (1:4) cement mortar of 125 mm thick for the extension of existing toilet with necessary curing .	Sq.mtr	7.67		
4	Platering to wall with sand / cement mortar (1:4) in 20mm thick including curing complete.	Sq.mtr	15.34		
5	Painting with cement based paint (snowcem) to the interior and exterior walls of toilet in two coats with proper curing etc.	Sq. mtrs	37.00		
6	Providing new shade to the toilet and its approach through "Jindal " colour coated galvanised sheet on necessary M.S.frame work , painting / applying on coat primer and two coats synthetic enamel paint with fixing through self tapping screw and finally fixing rain water pipe of 4" dia (supreme brand) for easy draining out of rain water.	Sq.mtr	24.50		
7	Flooring work to new toilet with non skid / mat finish ceramic tiles (12' x 12") in proper level over cement / sand mortar bed (1:4) with pointing the joints etc. complete.	Sq. mtrs	23.08		
8	Fixing of wash basin, gents' urinal, exhaust fan, etc. (after examining the commode in good condition order) including necessary plumbing work complete.	Whole job	L.S.	One item	
9	Fixing the old door in proper place after necessary repairing and painting etc. complete.	One item	L.S.	Whole Job	
				- Total before tax	
				Tax if any	
				Net Total	

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **21-06-2024** & close on **27-06-2024**. The Selection /opening will be made at the Principal's office at **3:00 P.M. on 28-06-2024**.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

Madhumanjari Mandal
Dr. Madhumanjari Mandal 21/6/24
Principal

Principal
Scottish Church College
Kolkata

