

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /08/2024-25 Dated 03-07-2024

Contact: Mr. Shibnath Bhattacharyya (M-98362-72199)
Mr. Monojit Mondal (M- 9123086001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for repair and renovate the existing soil pipe line , with providing new pits , of Jubilee Building within Scottish Church College Complex.

Sl. No	Description of Items	Unit	Quantity	Rate	Amounts
1	Carefully dismantling all types of masonry including cement concrete plain or reinforced with cleaning debris	Cumt	2.17		
2	Earth work in excavation for construction of new pits, within the old pits in the same alignment with removing old soil pipe line for easy cleaning / washing the pits after examination, if any chocked happens with cleaning debris after work.	Cumt	4.76		
3	Spreading silver sand to found of pits also the alignment of pipe line from old pits in a thickness of 10 cm with due saturation and ramming etc.	Sq.mtr	3.61		
4	Single layer brick flat soling of picked jhama brick including ramming dressing to proper level and fitting the joints with sand.	Sq.mtr	6.12		
5	Cement concrete with graded stone ballast with graded stone ballast (40 mm size) excluding shuttering in (1:3:6) proportion including curing	Cumt.	0.12		
6	Brick work with 1 st class brick in cement mortar (1:6) in foundation and plinth with caring complete.	Cumt.	0.97		
7	Plaster to neat wall of pits and other walls of existing pit with cement and sand mortar (1:4) in 20 mm thick including caring complete.	Sqmt	13.82		
8	Provision for new RCC cover (0.80 x 0.80) in 0.08 mt. Thick embedding with iron ring , for easy lifting) to all the pits , as most of them damaged /broken, with elevating a little from G.L.	Unit	07		



9	Provision for laying 4" UPVC supreme pipe under existing old damaged line with fitting silver sand on pipe before laying cement concrete. (to be measured as per actual execution)	Mt.	10		
10	Controlled cement concrete (1:2:4) with well graded 20 mm size stone chips, excluding shuttering and reinforcement , in ground floor including curing in 10 cm thick (AV)	CUMT	1.57		
11	Checking and examining the existing drainage / soil pipe line towards mother pit of sewerage line including cleaning and petty repairing also shifting of deposited garbage for easy flow of waste water without any obstruction.	One item	Whole job	L.S.	
12	Provision for repairing the surface drain to the north side of main building to prevent any stagnation with clearing for easy flow of water	One item	Whole job	L.S.	
Total amount before tax					
Tax, if any					
Total amount after tax					

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **03-07-2024** & close on **09-07-2024**. The Selection /opening will be made at the Principal's office at **3:30 P.M. on 10-07-2024**.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

Madhumanjari Mandal

Dr. Madhumanjari Mandal
Principal

3/7/24

Principal
Scottish Church College
Kolkata

