

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /10/ 2024-25 Dated 12-07-2024

Retender of Estate/SCC /07/2024-25 Dated 03-07-2024

Contact: Mr. Shibnath Bhattacharyya (M-98362-72199)
Mr. Monojit Mondal (M- 9123086001)

Appropriate quotation is invited in sealed cover from eligible bidders'/suppliers/vendors for

A- construction of proposed toilet by transforming the existing building to back side of play ground at Bagmari, Kolkata with the following specifications:

Sl. No.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
1	Dismantling the thatched room from the very entrance of building with cleaning and also the dumped unserviceable materials around the building beyond the area .	One item	Whole job	L.S.	
2	Preparing temporary scaffolding work with bamboo and rope with necessary platform for execution of work .	Sq.mt.	50.40		
3	Carefully deplastering/removal & damaged and saline effected plaster with cleaning brick joints from old mortar , through chisel rods and brush including cleaning debris	Sq.mt.	50.40		
4	1 st class brick work with cement and sand mortar for partition wall and parapet (1:6)	Cumt	1.81		
5	Plastering work with cement /sand mortar (1:4) in 20 m.m. to 25 m.m. thick mixing with water proofing compound with curing complete.	Sq.mt.	57.10		
6	Painting work with snowcem to the inside walls and parapet wall of building in two coats with curing	Sq.mt.	57.10		
7	Flooring with non-skid /mat finish ceramic tiles (12 "x12") in proper level on cement /sand bed (1:4) with pointing the tile joints matching to the tile including finishing after chipping out the existing base etc.	Sq.mt.	8.42		
8	Fixing /laying glazed tiles to the walls (ht: 1.50 mt.) all around the toilet with cement /sand mortar (1:4) including pointing , finishing etc.	Sq. mt	25.20		



9	Provision for fixing Aluminium Door in 'AL' frame work with frosted glass at top and laminated ply at bottom with locking arrangement.	Sq. mt	2.70		
10	Provision for repairing the existing doors & windows with necessary painting	One item	Whole job	L.S.	
11	Provision for fixing & necessary fitting i.e. commode with cistern, wash basin, , exhaust fan and squatting plate. at 'ladies toilet with other related fitting with laying soil pipe etc as plumbing	One item	Do	Do	
12	Stretching of water connection from out side by installing a pump with over head tank (500 litres) including all, spot to be identified by Authority . (App: ¾" pvc pipe 80'-0" with adding connection all)	Do	Do	Do	
13	Plinth protection (1.00 mtrs width) to all around the Building to prevent capillary action including (soil cutting , + BF soling + 50 mm cement concrete + plastering) complete in all respect with curing as directed	Sq. mts	31.20		
14	Necessary electric work to the toilet for electric point of bulb , exhaust fan etc with necessary casing wiring.	One Item	Whole Job	L.S.	
15	Provision for M.S. Gate to enter the area of ladies toilet area with fixing , painting & supply	Do	Do	Do	
16	Construction of a Septic Tank (4.75 x 1.50 x 1.80) mt. with necessary soil cutting, B.F.S., base concrete (1:2:4) in 0.80 mt. Thick with 25 mm thick B/work all around , 13 mm thick partition wall including plastering (1:3) and neat cement punning inside with 0.10 mt R.C.C. slab on top with C.I. cover including a soak pit of 0.60 mt. dia as per norms .	One Item	Do	Do	
				Total before tax	
				Tax if any	
				Net Total	



B- Dismantling of dilapidated building /structure with sorting the serviceable materials to the back side of College Play Ground at Bagmari

Sl. No.	Description of Item	Unit	Quantity.	Rate	Amount (Rs.)
1	Carefully dismantling all types & masonry excepting cement concrete plain or reinforced with taking great care and if necessary rope ladder and bamboos may be hesed with necessary rope & plank (actual measurement to be taken before execution) with cleaning.	Cumt	53.5		
2	Sorting of serviceable materials i.e. wooden members, bricks, brick tiles and wooden frame work any from the debris with stacking in a suitable place (materials to be identified by the authority before execution)	Cumt	10.70		
Total before tax					
Tax if any					
Net Total					



C. Repair to staff room and other rooms i.e. toilet, electrical room and store shed to the very entrance of college play ground complex at Bagmari.

Sl. No.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
1	Providing temporary scaffolding work with bamboo and rope with necessary platform for the execution of work (to inside and outside)	Sq.mtrs	60		
2	Carefully deplastering /removal of damaged and pulverized plaster with cleaning the brick joints from old mortar through chisel rod and brash including cleaning debris.	Sq.mtr	57.30		
3	Plastering work with cement /sand mortar (1:4) in 20mm & 25 mm thick mixing with water proofing compound with curing complete	Sq.mtrs	80.35		
4	1 st class brick work with cement and sand mortar (1:6) for parapet work	Cumt	0.44		
5	Printing work with snow cem to the inside walls and room , toilet and parapet in two coats with curing	Sq.mts	80.35		
6	Artificial stone flooring over to existing bed laying cement concrete (1:2:4) in the thickness 0.05 mt after raking out the bed following 10mm thick plaster with neat cement punning including finishing & curing	Sq.mtrs	13.47		
7	Provision for refixing the door at staff room and electric room with repairing the door of toilet with the available corrugated , available at site.	One item	Whole job	L.S.	
8	Stretching of electric line to staff room and electric room in a systematic way.	One item	Whole job	L.S.	
9	Provision for fixing aluminium window on "AL" frame work with frosted glass including aluminium net (38mm x 38mm) in its out side	Sq. mtrs	0.67		
10	Providing new shade through M.S. square pipe of 50mm x 50mm and 75 mm x 75mm through parallel to longer and shorter span with applying one coat Primer and Two coat enamel paint with fixing / laying 'JINDAL' blue sheet with self taping screw including removing the old existing damage corrugated tin sheet, including all.	Sq mtrs	17.55		
11	Replacing the damaged M.S.Sheet floor of (12 guage) security room with necessary support from bottom after removing the	One item	Whole Job	L.S.	



	damaged sheet , with necessary priming & painting on both side of sheet.				
12	Cleaning and washing the exterior surface of security room with face from dust , dirt etc.	One item	Whole Job	L.S.	
Total before tax					
Tax if any					
Total after tax					

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from 12-07-2024 & close on 21-07-2024. The Selection/opening will be made at the Principal's office at 3:00 P.M. on 22-07-2024.

The Authority of the College reserves the right/discretion for selection based on experience, amount, quality of the bid & bidder.

Madhuranjari Mandal
Dr. Madhuranjari Mandal 12/7/24
Principal
Principal
Scottish Church College
Kolkata

