

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /17/2024-2025 Dated 10-09-2024

Contact: Dr. Amitava Roy (M-9433590282)

Appropriate quotation is invited in sealed cover from eligible bidder /supplier/ vendor for supplying of electrical line for for Room- P6 & P7 (Main Building, 1st Floor) at Scottish Church College.

No.	Description of Item	Qty	Unit	Rate (Rupes)	Amount (Rupees)	Remarks
1	Wiring for 3 pin 6A plug point on board with 1.5sq mm. FR PVC insulated cooper conductor cable, including providing and fixing 3 pin 6A modular type socket outlet on switch board (in surface/recessed pvc conduct wiring system), and 6A modular type switch earthing the third pin etc. as required.	10	Point			
2	Supplying ad fixing suitable size GI box with modular plate and cover in front on surface or in recess, including and fixing 6 pin 5/6A modular socket outlet &15/16A modular switch, connections etc. as required.	15	Each			
3	Supplying and fixing UNIVERSAL SOCKET point on existing switch board with necessary connections etc. required	5	Each			
4	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 1 no. HDMI Cable Port & 1 no. TV Socket outlet point connections etc. as required	1	Each			
5	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 1o. Earthpoint connections etc. as required.	1	Each			
6	Supplying & fixing suitable size GI box with modular plate and cover in front on surface or in recess including providing and fixing 25A modular socket outlet	2	Each			



7	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FLRS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.				
7.1		20	Mtr.		
7.2		45	Mtr.		
7.3	2x 1.5 sq.mm + 1x 1.5sq.mm earth wire	150	Mtr.		
7.4	2x2.35 sq.mm+1x 2.5 sq.mm earth wire 2x4 sq.mm + 1x 2.5 sq.mm earth wire Cat 6	0	Mtr.		
8	Subhead-2 (Main Panel): Outgoing: 100A, 4P, MCCB,	2	Each		
9	4 Way TPN MCB DB, Double Door	1	Set		
	Main Incomer: 40A, 4P, MCB, "C' Curve				
	Outgoing: 6 to 16A SP, MCB, "C" curve				
10	6 Way VTPN MCB DB, Double Door	0	Set		
	Main Incomer: 100a, 4P, MCCB				
	Outgoing: 6 to 20A SP, MCB, "c" curve				
11	Supplying and fixing 63A, 415 V TPN MCB Isolator inside Thermoplastic Polycarbonate IP65 MCB Enclosure complete with connections, testing and commissioning etc. as required.	1	Each		
12	CABLE Supplying, laying/ fixing of one number PVC Insulated and PVC sheathed/ XLPE power cable of 1.1 KV grade aluminium conductor armoured cable of following sizes on wall/surface/ cable tray/ cable trench clamped with 1 mm thick saddle etc. as required.				
12.1	31/2C x 25 Sq.mm.	70	Mtr.		
12.2	4C x 16 sq.mm armoured AL cable	0	Mtr.		
12.3	4C x 10 sq.mm Armoured AL cable	0	Mtr.		
12.4	4C x6 sq.mm Armoured AL cable	0	Mtr.		
13	Supplying and making end termination with brass compression and aluminium lugs for following size of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1				
13.1		8	Each		



13.2	KV grade as required	0	Each			
13.3	31/2C x 25 sq.mm	0	Each			
13.4	4C x 16 sq.mm Armoured AL cable 4C x10 sq.mm Armoured AL cable 4C x6sq.mm Armoured AL cable	0	Each			
14	Supply, installation, testing & commissioning GI Perforated Cable tray (Hot Dip Galvanized) of best quality with necessary arrangement ets. As required.:	0	Mtr.			
14.1	200 mm width X25 mm depth X	0	Mtr.			
14.2	1.6 mm thickness 150 mm width X 25 mm depth X	0	Mtr.			
14.3	1.6 mm thickness 100 mm width X 25 mm depth X 1.6 mm thickness	0	Mtr.			
15	(Earthing): GI PIPE EARTHING Supply, installation, testing, and commissioning of earthing station with 40 m. wall thickness medium duty (as per IS9295-1983) 2 mtr. Long perforated hot dipped GI pipe earthing electrode complete with all required accessories like GI nut bolt and includes supply and construction of brick masonry chamber/ Inspection Pit with heavy duty CI frame and hinged cover(450 x 450mm) for body earthing of electrical equipments as per specification, relevant standard and drawings.	1	Nos.			
16	GI WIRE Supplying, laying and connection of earthing strips shall run on wall/ cable trench below the earth soil (including excavation) to equipment Neutral/ equipment body with accessories like earthing clamp, saddle etc. 8SWG GI Wire.	70	Mtr.			
16.1						
16.2	10 Copper Wire	0	Mtr.			
	Total					
	ADD 18% GST					
	Net Total					



This quotation is to be addressed to the Principal, Scottish Church College and has to be submitted to the Principal's office in Scottish Church College, at 1 & 3 Urquhart Square, Kolkata – 700 006, in due prescribed format on working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from 10-09-2024 & closed on 16-09-2024. The Selection /opening will be made at the College office at 3:00 P.M. on 17/09/2024.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

Madhumanjari Mandal

Dr. Madhumanjari Mandal
Principal

10/9/24

Principal
Scottish Church College
Kolkata