

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /31/2024-2025 Dated 03-03-2025

Contact: Mr. Shibnath Bhattacharyya (M-98362-72199)
Mr. Monojit Mondal (M- 9123086001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for-
Providing " Tin Shed all around of the Exterior wall of Main Building of College (over roof)
and extension of toilets with other related works : with the following specifications

SL No.	Description of Item	Unit	Quantity	Rate	Amount
1	Dismantling the old damaged " asbestos sheet " from the covered area of machinery over roof with stacking the serviceable materials & clearing debris	Sq.mt	17.85		
2	Providing new shade through M.S. Frame work of 75 mm x 38 mm (50mm x 25mm) and (75 x 75) mm vertical post @ 03mt c/c with applying one coat primer and two coats enamel painting with fixing / laying " Jindal " Blue sheet with self tapping screw and finally fixing rain water pipe (4" Ø) in supreme brand for easy drainage (height of sheet to be maintained as for surroundings)	Sq. mt	103.00		
3	Preparing temporary scaffolding work with bamboo and rope with necessary. Platform (for the work of damage Wall and broken cornice , damaged chaja,/ Sun Shade to all around the exterior surface over roof , back side of zoology building and exterior walls of Room no-N2, and dismantling after work	Sq. mtrs	567.50		
4	Carefully deplastering / removal of damaged and saline effected plaster with cleaning Brick joints from old mortar with brush and chisel rods including cleaning debris	Sq.mtr	35		
5	Replastering with lime / sand mortar (1:3) in 20mm to 25 mm thick mixing with water proofing compound with curing complete .	Sq. mtr	35		



6	Repairing to the damage bead with plastering to the projected parapet of building (south direction and S/east corner) with necessary Brick work and plaster with (1:3) lime mortar by maintaining existing clue available at site with raking out to deep seated roots and removing of tree (Main Building)	Sq. mtr	10.95		
7	Repairing to the damaged / perforated chajas (back of Zoology building) and sunshade (big & small) to west and south exterior wall of Room no-N2 after raking out old mortar / concrete and placing new concrete (1:2:4) with necessary plastering and finishing including curing complete . (both side)	Sq. mtr	12.45		
8	Repairing to broken and damaged glass panes to the windows of Zoology building and N2 building with necessary patty and finishing complete	Pcs	7		
9	Repairing to the doors and windows by replacing necessary frame work (2 nos) and louvered type leaf repairing (partly) (7 nos) with the help of new wood including fixing the missing fittings to bring all to doors and windows in proper position to all around the main building over roof .	No No	2 7		
10	Scraping and cleaning of moss , blisters and old painted flaked area with black patches from the projected building parapet of exterior surface of main building over roof with great care through scrapper/ sand paper.	Sqmt	386.00		
11	Providing and applying one coat primer with two coats weather proof exterior painting work including smoothening surface. (ICI/ Berger)	Sq. mt	286.00		
12	Painting to all wooden doors , windows and other M.S.windows with synthetic enamel paint IN Two coats after preparing base etc . (ICI/ Bursar)	Sqmt	164.74		
13	Scraping and cleaning the inside wall of corridor in front of proposed " Zonal Centre " from old dampness spot (after examination weather seepage stopped or not) with ceiling and adjoining area with great care through scrapper/ sand paper .	Sqmt	62.5		



14	Two coats lime wash with best quality lime mixing with D.DL./glue with smoothing surface including all.	Sq. mts	62.5		
15	Provision for shifting of different tools, apparatus and other materials to a safe place from the surrounded area over roof and opening the other end for easy movement etc.	One item	Whole job		
16 (a)	<u>Toilet extension with repairing the existing one</u> Preparing temporary scaffolding work with bamboo and rope with necessary platform and dismantling after work	Sq.mtr	13.50		
(b)	Carefully dismantling of all types of brick masonry (as per requisite) also damaged corrugated tin shade of existing toilet on roof with its door .	One item	Whole job		
©	Raking out the existing tarfelt with great care from where new toilet to be erected	Sq. mtr	10.00		
(d)	Controlled cement concrete (1:2:4) with well graded 20 mm stone chips , excluding shuttering & reinforcement, in 8 cm thick including curing complete	Sq. ft	0.80		
(e)	1 st class brick work with (1:4) mortar of 125 mm thick for the extension of existing toilet also the old toilet (as per requirement)m with curing complete	Sqmtr	28.34		
(f)	Plastering to wall with sand / cement mortar (1:4) in 20mm thick including curing complete	Sq. mtr	55.68		
(g)	Painting with cement based paint to the interior and exterior walls of toilet in two coats with proper curing etc.	Sq.mtr	164.74		
(h)	Providing new shade to the existing and proposed toilet through " Jindal" colour coated galvanised sheet on necessary M.S. Frame work (for roof only) after primering and painting two coats with synthetic enamel paint , with fixing through self tapping screw and finally fixing through rain water pipe of 4" dia (supreme brand)for easy draining out water to nearest roof out let . Frame work : (50 x 50) mm shorter span (50 x 38) mm longer span.	Sqmt	18.00		
(i)	Flooring work to new toilets with non skid / mat finish ceramic tiles / vitrified tiles (as suggested by Authority) in proper level over cement sand bed (1:4) with pointing to tile joints complete	Sqmt	8.05		



	(shade of tile to be selected by Authority) best quality.				
(j)	Fixing / Laying glazed tiles to the inner walls of toilet (1.00 mt ht) with cement/ sand (1:4) mortar bed including finishing (shade of tiles to be selected by Authority) best quality.	Sq.mt	14.70		
(k)	Stretching electric line to the old and new toilets with necessary points of light , exhaust fan etc (As desired by Authority) also to the bottom of newly erected tin shade including cost of materials through conduct pipe	One item	Whole job		
(L)	Fitting and fixing of necessary fixtures to the toilets with modern fittings i.e. Basin, Commode with cistern except existing toilets) shower, mirror etc. (as desired by Authority) and other related s/steel fitting with necessary plumbing work and stretching water connection in proper way with complete.	One item	Whole job		
(m)	Laying /fixing of soil pipe , drainage pipe from new toilets to outlets with examining / checking the existing out – let and connecting accordingly with repair to the old damage c.i. pipe / connection if any for easy flow of waste materials and water to main drain /tank with necessary fitting including all.	One item	Whole job		
(n)	Fixing of pvc doors in good and hard quality to new toilets and old also including fitting and fixing complete . (colour to be selected by Authority)	Each	3 nos		
17	Rearranging / Shifting of existing rain water pipe from the front of old toilet and others with stretching the same after execution of new toilets and laying 25mm Ø pvc pipe through the door, beneath and over roof to collect AC wastage water (to prevent fallen on roof) and continued to nearest drain.	One Item	Whole Job		
18	Providing / Laying new blue zindal tin sheet after replacing to old/ damaged asbestos sheet over the existing wooden frame work with fixing in proper way through self-tapping screw / hook (whichever is necessary) with fixing rain water pipe to the edge of 4" dia supreme brand pipe with attaching to the pipe of newly shade including all.	Sqmt	26.25		
19	Gas Cutting to the other side of covered area of asbestos shed over roof for easy	One Item	Whole Job		



	brand pipe with attaching to the pipe of newly shade including all.				
19	Gas Cutting to the other side of covered area of asbestos shed over roof for easy movement from one side to other during monsoon.	One Item	Whole Job		
20	Water tightening work to the floor of Asbestos cover area on roof by applying two coats Asian paints smart care damp proof liquid after preparing base form moss , lichen, any algae / dust etc. with finishing	Sq.mt	16.48		
21	Cleaning / shifting of all types debris / unwanted materials from the work site to outside of College Campus after necessary instruction of Authority	One Item	Whole Job		
				Total	
				Tax, If Any	
				Total after Tax	

This quotation is to be addressed to the Principal, Scottish Church College and has to be submitted to the Principal's office in Scottish Church College, at 1 & 3 Urquhart Square, Kolkata – 700 006, in due prescribed format on working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **06-03-2025** & closed on **12-03-2025**. The Selection /opening will be made at the College office at **2:00 P.M.** on **13-03-2025**.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

Madhumanjari Mandal
Dr. Madhumanjari Mandal
Principal

6/3/25

Principal
Scottish Church College
Kolkata

