

Scottish Church College

Kolkata

Date : 10/05/2025

CORRIGENDUM

in

Tender Estate/SCC/04/2025-2026 Dated 08.05.2025

**This is a correction intimated in regard to the uploaded Tender No.
Estate/SCC/04/2025-2026 Dated 08.05.2025 as serial Nos. 7-13 were missing.
The corrected Tender is uploaded on 10/05/2025.**


Dr. Madhumanjari Mandal
Principal

Principal
Scottish Church College
Kolkata

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /04/2025-2026 Dated 08-05-2025

Contact: Dr. Bidisa Sinha (M- 90079 50787)
Dr. Satadal Bghattacharyya (M-9433482779)
Mr. Shibnath Bhattacharyya (M-98362-72199)
Mr. Monojit Mondal (M- 9123086001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for Maintenance and repairing to kitchen and surroundings with toilets from 2nd fl. To 4th fl. Of Lady Jane Dundas Hostel of Scottish Church College of the following :

SL.No.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
1	Dismantling the wall of existing shelve, washing area, shelve & kota stone and between to pillars of existing kitchen (as per requirement) with cleaning debris	One item	Whole job	L.S.	
2	Raking out the damaged / undulated floor of kota stone marble chips floor at kitchen and dinning space of prevent stagnation of water with cleaning debris etc.	Sq.mt.	8.61		
3	Fixing /laying glazed tiles to the inner walls of kitchen, store place and dinner place area, as per requirement , with cement mortar(1:4) bed after raking out the damaged plaster and preparing base (Best quality shade of tiles), to be scheduled by authority	Sq.mt	133.80		
4	Flooring work to the raked out areas with kota stone / terrazzo floor, matching to surroundings, in proper level over cement bed (1:4) with painting to the joints complete	Sq, mt	9.43		
5	Controlled cement concrete (1:2:4) with well guarded 20mm stone chips, excluding shuttering of reinforcement 1n 8 cm thick to lift the floor , as demand, with curing complete.	Sq. mt	2.63		



6	1 st class brick work with (1:4) mortar of 125 mm thick for guard wall at washing area of kitchen and others with curing complete and plaster the same also.	Sq.mt	1.35		
7	Painting work with washable distemper to the interior walls of kitchen and store area to the coats after providing base including all	Sq.mt	186		
8	Painting to the all M.S. windows with grill, doors with synthetic enamel paint in two coats after preparing base i.e. oily short etc. (specially from windows)	Sq. mt	19.92		
9	Provision for fixing to shelves at kitchen and store area (0.90 X 0.45 X 2.00) MT making with plywood with aluminium channel with sun mica base including fitting, fixing painting with lock and key arrangement including all.	UNIT/NOS	02		
10	Stretching of G.I. pipe work with line with necessary plumbing work , as per requirement with necessary fitting and Bib cock etc. with a little repair and execution of electric work including all.	One item	Whole Job		
11	<p>Toilets related work for all floors (Specially 2nd to 4th floor)</p> <p>(A) Preparing temporary scaffolding work with Bamboo and rope with necessary platform and dismantling after work.</p> <p>(B) Provision for checking and examining the all pipe lines related to toilets for all floors with changing the damaged / cracked P.V.C. fitting to prevent all kind of dropping water with cleaning any chocked , if happens including all for easy flow of waste water etc.</p>	<p>Sq.mt</p> <p>One item</p>	<p>320</p> <p>Whole job</p>		



	<p>(C) Polishing the existing terrazzo floor, outside of toilet and washing area, from 2nd to 4th floor of both sides, which are going to use by students, after cleaning the block patch with machine with necessary deep cutting through hand grinding machine for making a slope to prevent any stagnation in such a way to prevent any stumble etc.</p> <p>(D) Provision for scrapping and cleaning of damped unwanted debris over the preparing sunshade which was covered by the synthetic ply through aluminium frame work will uprooting deep seeded root of trees.</p> <p>(E) Provision for M.S. grill jail for to all windows toilet of both direction, specially from 2nd to 4th fl floor to prevent any droppings from toilets over sunshade including fixing / fitting</p>	<p>Sq. mt</p> <p>One item</p> <p>Each (0.60 x 0.90 x) mt.</p>	<p>60.54</p> <p>Whole job</p> <p>36</p>		
12	Provision for removing synthetic ply which were fixing through aluminium frame work to camouflaze the toilet area of each side. (Some portion has been damaged and missing with great care to keep proper vigil whether any damaged is going on or not. Also to keep clean the top of sunshade time to time.)	One item	Whole job		
13	Repairing to al sunshade if any after raking out damaged portion with necessary cementing plastering etc as pre-requirement to prevent	One Item	Whole Job		



14	Removal of debris and other unserviceable materials beyond the compound after completion of work	One Item	Whole Job		
Total					
Tax if any					
Total after Tax					

This quotation is to be addressed to the Principal, Scottish Church College and has to be submitted to the Principal's office in Scottish Church College, at 1 & 3 Urquhart Square, Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **08-05-2025** & close on **14-05-2025**. The Selection /opening will be made at the Principal's office at 3:00 P.M. on **15-05-2025**.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

M. Mandal
Dr. Madhumanjari Mandal
Principal

Principal
Scottish Church College
Kolkata

